

Bill No 1: BOREHOLE DRILLING	TOTAL COST \$
Mobilization of personnel, Equipment and materials	\$388.88
Site preparations and machine setting	\$291.00
Borehole Construction	\$1,920.00
Consumables to include:	\$2,430.00
a) Fuel and Lubricants	
b) UPVC Casing pipes	
c) Drilling foam	
d) Gravel Packing Materials	
e) Cement and drilling water	
Casting of Sanitary seal	\$121.00
Installation of Cement Grouting	\$97.22
Installation of Gravel Pack	\$194.44
Well Develepment	\$315.97
Clearing Site	\$48.60
Preparation of completion report	\$24.30
TOTAL BILL NO.1	\$5,831.41

BILL NO.2 SOLAR PUMP PLATFORM CASTING AND INSTALLATION	
Construction platform slab	\$153.00
Supply and installation of a stainless steel submersible solar pump with max. 100m water lift	\$489.00
Supply and installation of PVC pipe 2	\$184.00
Supply and installation of stainless connecting Rods	\$364.00
automatic solar water pump regulator 20-60A	\$350.00
Supply and installation of 350w solar system including pannels and structure	\$650.00
1500 liters water tank	\$225.00
Supply and installation metal tank structure	\$785.00

BILL NO.2 TOTAL	\$3,200.00
------------------------	-------------------

BILL NO.3 HYDRO-GEOLOGICAL SURVEY AND TRANSPORT	
Hydro-Geological survey and transport	\$500.00

TOTAL COST OF BILL 1,2 AND 3 **\$9,531.41**